Sl. No.	Items of work	Per	Quantity
20	White and colour washing	Sqr.	32·85
21	Chocolate painting to doors and windows ...	,,	4·46
22	Wood-oiling to rafters and collars ...	,,	4·00
23	Chunam pointing to basement and plinth with hard ground morts and centring the joints.	Sqrs.	1·68
24	Clearing the site and levelling the ground and unforeseen charges.	L. S.	L. sum
25	Improving the flooring of Dispensary by removing the old-flooring tiles.	Sqr.	2·80
26	Flooring with first class 9" square Mangalore tiles on concrete bed with pointing.	,,	2·80

N. G. KRISHNA IYENGAR,
Executive Engineer.

MYSORE RAILWAYS.

Abstract Notification dated 21st September 1928.

Attention of the intending contractors is hereby invited to the notice calling for tenders for providing additional accommodation for the Railway Dispensary and the Assistant Surgeon's Quarters near Mysore Railway Station, published in pages 965-966 of Part VI of the *Mysore Gazette*, dated 20th September 1928. Tenders will be received any day up to 2 P.M. of 15th October 1928.

M. RAMAIYA,
Executive Engineer.

HASSAN DIVISION.

Notice dated 24th September 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M., 12th October 1928, for Extending Feeder Channel of Bagur Tank, Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the Feeder Channel of Bagur Tank, Channarayapatna Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract estimate for extending the Feeder Channel to Bagur Tank, Registered No. 177 of Channarayapatna Taluk.

Items of work	Per	Quantity	Remarks
Feeder Channel.			
1. Earthwork cutting	C.yds.	30,051	
2. Forming into bank out of spoil	,,	1,580	
Relieving weir length 46' long at C. S. 14.			
3. Burnt stone in surki mortar	C.ft.	1,034	
4. Burnt stone slab 6" thick	S.ft.	165	
5. Plastering with surki mortar	Sqr.	4·70	
6. Rough stone work, new	C.yds.	137	
7. Excavating foundation and forming	Lump sum	rupees	
Rapid at C. S. 24 (drop 25' long).			
8. Burnt brick in surki mortar	C.ft.	206	
9. Burnt stone slabs 6" thick	S.ft.	69	
10. Plastering with surki mortar	Sqr.	1·38	
11. Rough stone work, new	C.yds.	101	
Closing the breach No. 1 with core wall.			
12. Brick in surki mortar	C.ft.	180	
13. Excavating foundation	Lump sum	rupees	
Silt Dams.			
14. One at breach No. 2 and one in halla from Honnenally Tank.	Each	2	

R. L. STEELE,
Executive Engineer.

SHIMOGA DIVISION.

No. 502, dated 26th September 1928.

It is hereby notified for information that the following Savings Bank Deposit Books are lying in this office unclaimed for a number of years and to state that if the parties concerned fail to receive books within the end of October 1928, from the undersigned, the amounts of deposits will be finally credited to Government.

Account No.	Name	Amount
		Rs. a. p.
3402 ...	Veeraraghava Iyer, Maramet Sub-Overseer ...	17 2 2
3835 ...	S. Krishna Iyengar, Manager ...	45 2 5

M. A. SRINIVASACHARI,
Executive Engineer.

KADUR DIVISION.

Notice dated 26th September 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 15th October 1928, till 3 P.M., for the construction of a Girder bridge across the Bandihalla in 4/16 of Narasimharajapura-Balehonnur Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalore between the hours of 11 A.M. and 5 P.M. on working days.